




REQUIRED ATTACHMENT:

YAKIMA COUNTY GENERAL SITE PLAN

Note: Producing the site plan from this template is preferred, however, the template can be substituted for your own drawing (computer aided is acceptable).

Site plan must be drawn with blue or black ink



LOT COVERAGE CALCULATION

a) Dimension(s) of existing structure(s) _____ SQ FT
b) Building addition/new structure(s) dimension(s) _____ SQ FT
c) Existing paved area(s) (driveways, walkways, patios, etc.) TOTAL _____ SQ FT
d) Proposed paved area(s) _____ SQ FT
e) Total Impervious Surface (a+b+c+d = e) _____ SQ FT
f) Lot Size (1 acre = 43,560 sq ft) _____ SQ FT
g) Lot coverage (e/f x 100 = g) _____ %

MAP SCALE (check one)

Preferred Scale: 1 inch on the map = 20 ft on the ground Custom Scale: 1 inch = _____

*Square is 0.25" by 0.25"

PARKING CALCULATION (Reference Table 19.22 in YCC 19.22)

Spaces required: _____

Spaces provided: _____ Surface Type: _____

LOT INFORMATION

Parcel # (s): _____

Site Address: _____

BACKGROUND INFORMATION

Owner Name: _____

Site Plan Created by: _____

Address: _____

Contact Phone: (_____) _____ Date Created: _____

Required Site Plan Information:

	N/A	#	
<input type="checkbox"/>	<input type="checkbox"/>	1	Paper size: Minimum 8 1/2" x 11" up to Maximum size 11"x17"
<input type="checkbox"/>	<input type="checkbox"/>	2	Property Owner Name, Parcel Number and, Site Address
<input type="checkbox"/>	<input type="checkbox"/>	3	North Arrow shall be directed at top of the paper with the writing facing the same northern direction.
<input type="checkbox"/>	<input type="checkbox"/>	4	Drawn to scale. Example 1" = 25' or 1" = 50'
<input type="checkbox"/>	<input type="checkbox"/>	5	Background Information: Site Plan Created By, Address, Contact Phone #, & Date Created
<input type="checkbox"/>	<input type="checkbox"/>	6	Lot Coverage Calculation for all zones except AG, FW, MIN, R/ELDP-40, R-10/5 *
<input type="checkbox"/>	<input type="checkbox"/>	7	Aerial photos are not acceptable
<input type="checkbox"/>	<input type="checkbox"/>	8	Property line dimensions of all lot(s) involved in the project.
<input type="checkbox"/>	<input type="checkbox"/>	9	The location, width and purpose of all easements (utility, access and/or irrigation) on the site and adjacent to the site with distances to proposed structures.
<input type="checkbox"/>	<input type="checkbox"/>	10	The distance from existing and proposed structures to the centerline of state, county, private roads, or access easement with name, dimension, surface type (paved, gravel or dirt) of road.
<input type="checkbox"/>	<input type="checkbox"/>	11	Existing or proposed driveway locations, Length, and Width.
<input type="checkbox"/>	<input type="checkbox"/>	12	Location, shape, size, gross floor area, height and types (i.e., house, garage, well house) of all existing and proposed structures, distance "minimum building setbacks" from the property lines and other structures, and the total lot coverage.
<input type="checkbox"/>	<input type="checkbox"/>	13	The location, right-of-way widths, pavement widths, curbs, gutters, culverts and names of all existing or platted streets or roads, whether public or private, and other public ways within the subject property or adjacent to any affected lots;
<input type="checkbox"/>	<input type="checkbox"/>	14	Location of well or water systems within 100 feet of the subject property or within a 100 foot well control zone and the distance from any structures within the well control zone. Label as Individual, 2-party, Group B, Group A. If located on another parcel note location on site plan.
<input type="checkbox"/>	<input type="checkbox"/>	15	Location of proposed or existing septic tank, drain field area, and extension area, as well as replacement areas and distances to structures and property lines
<input type="checkbox"/>	<input type="checkbox"/>	16	The location and dimensions of any existing and proposed utilities, streets, railroads, irrigation and drainage canals, easements and dedication of property within the subject property or adjacent to any affected lots;
<input type="checkbox"/>	<input type="checkbox"/>	17	Critical Areas/Shoreline: River, streams, creek, pond, floodplain, floodway, etc. on or abutting the site (Distance from structure to the ordinary high water mark of the river, stream, creek, etc.)
<input type="checkbox"/>	<input type="checkbox"/>	18	Show the existing topographic contours at intervals of not more than 5' when the ground slopes exceed 10%. Extend 100' beyond the boundaries of the site.

Building Division Application Site Plan Information:

	N/A	#	
<input type="checkbox"/>	<input type="checkbox"/>	1	Fire apparatus turnaround
<input type="checkbox"/>	<input type="checkbox"/>	2	For larger parcels, draw a simple plan showing the entire lot and indicate which area the new construction is to take place. Attach to the detailed section and submit both.
<input type="checkbox"/>	<input type="checkbox"/>	3	Distance of new structures from all property lines.
<input type="checkbox"/>	<input type="checkbox"/>	4	Location of Garage and Carport vehicle entrances.

Planning Division Application Site Plan Information:

	N/A	#	
<input type="checkbox"/>	<input type="checkbox"/>	1	Location and dimensions of all proposed exterior land uses.
<input type="checkbox"/>	<input type="checkbox"/>	2	Location of new and/or expanded public and private utility infrastructure.
<input type="checkbox"/>	<input type="checkbox"/>	3	Location of pedestrian and vehicular circulation patterns, sidewalks, trails and bicycle paths.
<input type="checkbox"/>	<input type="checkbox"/>	4	Location of structures on the adjoining lots, which may cause compatibility issues.
<input type="checkbox"/>	<input type="checkbox"/>	5	Proposed location and dimensions of community and other open space.
<input type="checkbox"/>	<input type="checkbox"/>	6	Existing and proposed landscaping, site screening, street trees and storm water drainage facilities.
<input type="checkbox"/>	<input type="checkbox"/>	7	The existing on-site sewage system components and reserve areas and the proposed location for on-site sewage systems and soil test pits for all affected lots not served by an on-site sewage system or other approved wastewater treatment system. The location of structures on the adjoining lots when within 100 feet of a well or on-site sewage disposal system;
<input type="checkbox"/>	<input type="checkbox"/>	8	Proposed contours and grading as they affect lot layout, streets, and drainage ways.
<input type="checkbox"/>	<input type="checkbox"/>	9	Location of adjacent public water, sewer main, fire protection systems and other underground facilities within or adjacent to the development.
Floodplain development:			
<input type="checkbox"/>	<input type="checkbox"/>	10	Description of the extent to which any watercourse will be altered or relocated as a result of the proposed development.
<input type="checkbox"/>	<input type="checkbox"/>	11	The boundaries of the 100-year floodplain, the boundaries of floodways where floodways have been established, and the 100-year base flood elevations where base flood elevations have been established.
<input type="checkbox"/>	<input type="checkbox"/>	12	The boundaries of the 10 and 25-year floodplain using the flood risk maps provided by Yakima County as part the mandatory pre-application conference.
<input type="checkbox"/>	<input type="checkbox"/>	13	Other information as may be required by YCC Titles 13, 16A, 16C or 16D.

*Lot Coverage is not specified within these zoning districts; however site screening may be required under Subsection 19.21.030(2)(f) and (g)